BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

MODIFIED SCHEDULE - B

Name of Work: Construction of Balance Work Compound Wall, DG Room, Office Room Parking area and Toilet at Samudhaya Bhavana Hegdenara (near Dry Waste Collection Centre) in Ward No. 06, Byatarayanapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
1	440.87	Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller)	Cum	220.32	Rupees Two Hundred Twenty And Paise Thirty Two Only
2	231.85	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m. In depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. after breaking of clods complete as per specifications.	Cum	283.02	Rupees Two Hundred Eighty Three And Paise Two Only
3	67.47	Providing and laying in position plain cement concrete of **mix M7.5 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	4976.70	Rupees Four Thousand Nine Hundred Seventy Six And Paise Seventy Only
4	177.75	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	3910.34	Rupees Three Thousand Nine Hundred Ten And Paise Thirty Four Only
	4.38	Qty Above 125%	Cum	3910.34	Rupees Three Thousand Nine Hundred Ten And
5	58.35	Providing and constructing granite / trap / basalt size stone masonry in **basement** with **cement mortar 1:6**, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification.	Cum	4814.52	Rupees Four Thousand Eight Hundred Fourteen And Paise Fifty Two Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

12/03
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92
12/03

No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
6	753.75	Providing and injecting chemical emulsion for Preconstructional anti-termite treatment, creating continuous chemical barrier under and around the column pits, walls, trenches, basement excavation, top surface of the plinth filling, junction of wall and floor, along the external perimeter of building, expansion joints, over the top surface of consolidated earth on which apron is to be laid, surrounding of pipes and conduits, with chloropyriphos emulisifiable concentrates of 20% concentration, including cost of chemical, diluting in water to one precent concentration, labour, HOM of equipments, complete as specifications.(Plinth area of building at ground floor only shall be measured)	Sqm	108.12	Rupees One Hundred Eight And Paise Twelve Only
	537.45	Qty Above 125%		108.12	Rupees One Hundred Eight And Paise Twelve Only
7	200.24	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	97.52	Rupees Ninety Seven And Paise Fifty Two Only
8	378.17	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	999.58	Rupees Nine Hundred Ninety Nine And Paise Fifty Eight Only
9	91.13	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams.	Cum	6345.16	Rupees Six Thousand Three Hundred Forty Five And Paise Sixteen Only
	64.03	Qty Above 125%		6345.16	Rupees Six Thousand Three Hundred Forty Five And Paise Sixteen
10	10.95	Providing and laying in position **reinforced cement concrete of design mix M20** with OPC cement @ 24kgs, with 12 mm and down size graded granite metal coarse aggregates @ 0.5175 cum and fine aggregates @ 0.345 cum with superplastisiser @ 0.225lts,machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor lever, including cost of all materials, labour, HOM of machinery, curing, complete as per specification.	Sqm	461.10	Rupees Four Hundred Sixty One And Paise Ten Only
	4.20	Qty Above 125%		461.10	Rupees Four Hundred Sixty One And Paise Ten Only
11	12.49	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **TMT Bars FE 500**	Tonne	58229.25	Rupees Fifty Eight Thousand Two Hundred Twenty Nine And Paise Twenty Five Only
	4.39	Qty Above 125%		58229.25	Rupees Fifty Eight Thousand Two Hundred Twenty Nine

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

12/03
Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92
12/03

Executive Engineer

No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
12	92.13	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to **ceiling** including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	193.98	Rupees One Hundred Ninety Three And Paise Ninety Eight Only
13	359.87	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	235.32	Rupees Two Hundred Thirty Five And Paise Thirty Two Only
14	452.00	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications.	Sqm	25.44	Rupees Twenty Five And Paise Forty Four Only
15	322.80	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	199.28	Rupees One Hundred Ninety Nine And Paise Twenty Eight Only
16	175.50	Providing and removing centering, shuttering, strutting, propping etc., and **removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm** including cost of all materials, labour complete as per specifications	Sqm	572.40	Rupees Five Hundred Seventy Two And Paise Forty Only
	85.95	Qty Above 125%		572.40	Rupees Five Hundred Seventy Two And Paise Forty Only
17	15.15	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications.	Sqm	278.78	Rupees Two Hundred Seventy Eight And Paise Seventy Eight Only
18	216.50	Providing and **removing centering, shuttering, strutting, propping etc.,** and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications.	Sqm	239.56	Rupees Two Hundred Thirty Nine And Paise Fifty Six Only
	313.86	Qty Above 125%		239.56	Rupees Two Hundred Thirty Nine And Paise Fifty Six Only
19	28.26	Supply and fixing pressed steel door frames size 125x65 mm manufacture from 1.25mm thick carbon steel or imported steel strips with mitred joints of 900 for door openings and sutters made out of seasoned honne wood, styles of 30mm, thick with lock rail of 160mm, width, top and side rails of 100mm, width width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be not proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years, this shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting wit enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc, complete the hollow portion of the frame to be filled with cement concrete1:2:4.	Sqm	3710.00	Rupees Three Thousand Seven Hundred Ten Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
20	1.08	Supplying and fixing pressed steel window frame of size 100x50mm manufacture from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 900degree for window openings and shall be suitable to fix M.S grills as per design and drawings using 12mm dia roads at 100mm centre to centre horizontally and two members of M.S flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S flats with 16mm size lugs, and 8nos, of 100mm size hinger, 4nos of butt stay pins and 4nos, tower bolts and shutters half paneled and half glazed with shutters made out of seasoned honne wood, styles of 30mm thick and 100 mm width and rails of 30mm thick and 100 mm width and using 4mm thick pin headed glass and panel, filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage, warp age and such other defects for a period of 3 years, this shall be as per approved drawin the work	Sqm	3945.32	Rupees Three Thousand Nine Hundred Forty Five And Paise Thirty Two Only
21	11.34	Providing & fixing factory made PVC Door frame of size 50x47 mm with a wall thickness of 5mm, made out of extruded 7mm rigid PVC foam sheet metered cut at corners & jointed 2No.s of 150mm long brackets of 15x15 mm M.S. Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufactures specification & direction of Engineer-in charge **SOLID PVC DOOR FRAME**	Sqm	552.26	Rupees Five Hundred Fifty Two And Paise Twenty Six Only
22	11.34	SOLID PANEL PVC DOOR SHUTTER Providing and fixing 30 mm thick factorily made rigid foam panelled door shutters made from M.S Tuvbe of 19 gauge thickeness size 19x19 mm tro styles and 15x15mm for top and bottom rails, coverted with heat moulded PVC channel of 5 mm thick sheet & 30 x 50mm wide to form styles & 5mm thick & 75mm wide PVC sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rails & bottom rail panelling of 5 mm thick 20mm wide PVC sheet fittled in te M.S Frame sealed to the styless & rails with 5 x 30mm PVC sheet beading on ewither sides & joined together with solvent cement adhesive etc., complete as per manufactures specification & direction of Engineer - in charge fixed to frames with 3 nos, of 75mm Aluminium hinges	Sqm	3365.50	Rupees Three Thousand Three Hundred Sixty Five And Paise Fifty Only
23	452.00	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foregin matter including preparing the surface even and sand paper smooth, cost of materials, labours, complete as per specifications	Sqm	69.96	Rupees Sixty Nine And Paise Ninety Six Only
24	322.80	Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications **with Primer**	Cum	83.74	Rupees Eighty Three And Paise Seventy Four Only
25	40.00	Providing colour glazed tiles of size 10mm thick for flooring, treads of steps and landing, laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing using white cement with matching colour pigment, including cost of materials, labour, complete as per specifications.	Sqm	1504.14	Rupees One Thousand Five Hundred Four And Paise Fourteen Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

12/03

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

12/03

No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
26	138.24	Providing skirting, dado, rises of steps with Colour glazed tiles 15x15cms 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, complete as per specifications.	Sqm	1037.74	Rupees One Thousand Thirty Seven And Paise Seventy Four Only
27	40.00	Providing and fixing on wall surface 4.0kg/sq.cm H.D.P.E rain down water pipes 90mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour, complete as per specifications.	m	451.56	Rupees Four Hundred Fifty One And Paise Fifty Six Only
28	0.00	Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufactures of blocks of approved size , shape and colour with a minimum compressive strength of 281kgs per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour, curing complete as per specifications.	Sqm	833.16	Rupees Eight Hundred Thirty Three And Paise Sixteen Only
29	5.00	Providing and fixing white vitreous china clay, flat back wash basin of size 630x450mm with pair of 15mm C.P brass pillar taps with C.I./M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets ,cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Unit	3931.54	Rupees Three Thousand Nine Hundred Thirty One And Paise Fifty Four Only
30	2.00	Providing and fixing white vitreous china clay, water closet Indian type (Squatting pan) of size 580mm with footrests, 100mm S or P trap, 10 litre low level, P. V. C. flushing cistern (all are approved make) with fittings, C.I. / M.S. brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with specials and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labours complete as per specifications.	Pan	5279.86	Rupees Five Thousand Two Hundred Seventy Nine And Paise Eighty Six Only
31	100.00	Providing and fixing to wall, ceiling and floor, high-density polyethylene pipes 6.00KGF/sq.cm. working pressure 32mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling an floor including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.	M	193.98	Rupees One Hundred Ninety Three And Paise Ninety Eight Only
32	50.00	Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 15mm dia nominal bore with fittings (medium grade weight 1.27 kg/mtr) B class including cost of all materials, labour, charges HOM of equipments and testing complete as per specifications.	m	366.76	Rupees Three Hundred Sixty Six And Paise Seventy Six Only
33	2.00	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	1007.00	Rupees One Thousand Seven Only
34	15.00	Providing and fixing unplasticised PVC connection pipe with brass union 15mm nominal bore 300 mm length of PVC connection including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Set	890.40	Rupees Eight Hundred Ninety And Paise Forty Only
35	40.00	Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	192.44	Rupees One Hundred Ninety Two And Paise Forty Four Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
36	1000.00	Supppying water storage tanks made of virgin polymer (LLDPE) with two layers outer black of blue and inner white layer of approved quality and make, conforming to	L	6.36	Rupees Six And Paise Thirty Six Only
37	150.00	**Groove Cutting :** Supplying ... dia 2mm/2.5mm thick heavy gauage PVC Conduit Pipe with bends metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out the conduit wherever necessary	Mtrs	43.00	Rupees Forty Three Only
38	75.00	25 mm dia 2mm thick		53.00	Rupees Fifty Three Only
39	4.00	Supplying and flush mounting teak wooden box with out front plank made of not less than 12mm thick wood after due groove cutting necessary masonry patch work complete	Each	68.00	Rupees Sixty Eight Only
40	4.00	8"X6"X3" (300X228X76mm)		52.00	Rupees Fifty Two Only
41	20.00	Supplying and fixing PVC/metal conduit accessories special type Junction Box	Each	29.00	Rupees Twenty Nine Only
42	25.00	Deep 32 mm Junction Box	No	33.00	Rupees Thirty Three Only
43	15.00	Fan Box 18 /SWG	Each	57.00	Rupees Fifty Seven Only
44	5.00	Point Wiring using copper wire with switch Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using Copper PVC insulated multi strand 2x1.5 Sqmm copper wire with a 6 Amps flush type SP control switch shall be fixed on the existing plastic sheet gang box the other end of the wires shall be terminated with sufficient loose length in a wood PVC round block complete for each outlet	Each	175.00	Rupees One Hundred Seventy Five Only
45	12.00	b) Medium point above 3mtr upto 6mtr from tapping point to out let via switch		260.00	Rupees Two Hundred Sixty Only
46	16.00	C) Long point above 6mtrs upto 10mtrs from tapping point to outlet via switch		368.00	Rupees Three Hundred Sixty Eight Only
47	10.00	Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate	Each	90.00	Rupees Ninety Only
48	3.00	4-5Way	No.	100.00	Rupees One Hundred Only
49	7.00	6Way	No	175.00	Rupees One Hundred Seventy Five Only
	5.00	8Way	No	195.00	Rupees One Hundred Ninety Five Only
50	5.00	10-12Way	No.	210.00	Rupees Two Hundred Ten Only
51	10.00	Supplying and fixing superior quality modula switch mounting polyorbonate plate with cecessary supporting back plate with required nos. of machines screwes, bolts nuts etc., complete on the existing metal/PVC box	Each	82.00	Rupees Eighty Two Only

EXECUTIVE ENGINEER-4
BBMP, BYATARAYANAPURA DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92
12/03

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
52	5.00	4 Modular	No	100.00	Rupees One Hundred Only
53	7.00	6 Modular	Sq.Cm	125.00	Rupees One Hundred Twenty Five Only
54	4.00	8 Modular	Nos	175.00	Rupees One Hundred Seventy Five Only
55	5.00	12 Modular	No	230.00	Rupees Two Hundred Thirty Only
56	50.00	Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate	Each	96.00	Rupees Ninety Six Only
57	20.00	6Amps 3way Socket.	No	165.00	Rupees One Hundred Sixty Five Only
58	7.00	Stepped Fan Regulator	No	530.00	Rupees Five Hundred Thirty Only
59	7.00	16 Amps one way switch	No	132.00	Rupees One Hundred Thirty Two Only
60	2.00	6Amps Bell push	No	115.00	Rupees One Hundred Fifteen Only
61	7.00	6/16 Amps univesla Socket	Cum	205.00	Rupees Two Hundred Five Only
62	4.00	TV / Telephone Socket	Rmtr	115.00	Rupees One Hundred Fifteen Only
63	4.00	Rj45/IO Oulet	Cum	525.00	Rupees Five Hundred Twenty Five Only
64	150.00	Wiring for lighting power curcuit using one of PVC insluated 1100v grade multistrand copper conductor single core cable in open or concealed system of wiring	Mtrs	150.00	Rupees One Hundred Fifty Only
65	1900.00	2.5 Sqmm	mtrs	25.00	Rupees Twenty Five Only
66	1900.00	4 Sqmm	mtrs	32.00	Rupees Thirty Two Only
67	75.00	6 Sqmm	mtrs	52.00	Rupees Fifty Two Only
68	12.00	Supplying an fixing one of 230 volts PBBC bakelite staight or slant batten holder and wiring with in 60w/230 Volts lamps	No	60.00	Rupees Sixty Only
69	12.00	Extra for supplying 4mm thick white plastic plate and convering for juncrtion boxese or size 80mm conduit using necessary machine screws	No	6.48	Rupees Six And Paise Forty Eight Only
70	2500.00	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches regulatoirs etc and fixing on existing wooden or metal box using NF screws	Sqcm	0.22	Rupees And Paise Twenty Two Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Byrathayanapura Division
BBMP, Bangalore-92

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
71	15.00	Supply patty type fluorescent tube light fitting of 4' - 36/40 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking, locking type brass contact holder mounted on double fold type sheet base fully wired for used on 230 Volts A C Supply including fluouresecent tube	Each	675.00	Rupees Six Hundred Seventy Five Only
72	15.00	Supplying of Incandescent lamps		14.00	Rupees Fourteen Only
73	4.00	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system KPWD SR 2007-08 (P-23, I-23) Regulator Model (Khaitan, Crompton Geaves, Orient, Polar, Bajaj, Usha, Havells, Almonard	Each	1800.00	Rupees One Thousand Eight Hundred Only
74	2.00	Supplying wall mounting fan suitable to operat		2400.00	Rupees Two Thousand Four Hundred Only
75	4.00	Supplying and fixing superior quality modula switch mounting polyorbonate plate with ncecessary supporting back plate with required nos. of machines screwes, bolts nuts etc., complete on the existing metal/PVC box	Each	82.00	Rupees Eighty Two Only
76	8.00	8 Modular		175.00	Rupees One Hundred Seventy Five Only
77	4.00	Supplying and fixing of modular switch / socket/Stepped electrical fan regulator / dimmer / telephone socket etc on existing modular switch plate	Each	96.00	Rupees Ninety Six Only
78	3.00	6Amps 3way Socket.		165.00	Rupees One Hundred Sixty Five Only
79	2.00	Supplying and fixing 32Amps security and energy savings DP switch with key tag suitable to operate on 230 Volts 50Hz AC supply & completely wired on existing box	Each	630.00	Rupees Six Hundred Thirty Only
80	2.00	Supplying an fixing one of 230 volts PBBC bakelite staight or slant batten holder and wiring with in 60w/230 Volts lamps	No	60.00	Rupees Sixty Only
81	2.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required	Each	560.00	Rupees Five Hundred Sixty Only
82	2.00	Supply and fixing polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc		285.00	Rupees Two Hundred Eighty Five Only
83	2.00	Supplying and fixing of porcelain fuse channel with cut out on existing wooden /panel using necessary nuts, bolts and washers etc complete		100.00	Rupees One Hundred Only
84	50.00	Supplying of LTUG cable having aluminium condutor PVC insulated shethed, galvnised steel, wire / steel tap armoured cable with PVC outer sheathing 1.1 KV class. 4 core 16 Sqmm	Mtr	215.00	Rupees Two Hundred Fifteen Only
85	50.00	Labour charges for laying of 1.1 K.V class UG cable **In existing trencg/duct 6Sqmm to 16 Sqmm)**	Mtr	11.00	Rupees Eleven Only
86	25.00	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete	Mtr	40.00	Rupees Forty Only
	10.00	Asphalt Cutting		60.00	Rupees Sixty Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

12/03

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

12/03

Sl. No.	Approved Qty.	Description	Unit	Rates	
				In Figures	In Words
87	5.00	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class	Mtr	240.00	Rupees Two Hundred Forty Only
88	1.00	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.,	No.	286.00	Rupees Two Hundred Eighty Six Only
89	2.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia,	No	3000.00	Rupees Three Thousand Only
90	230.00	Supplying and drawing UTP-CAT -E LAN calve (49/31)	Nos	35.00	Rupees Thirty Five Only
91	1.00	1HP Submercible centrifugal force pump of approved make with all necessary fittings including wiring switch board, starter etc., and Electronic Automatic Equipment (Programmable Logic Control)	LRQ	18000.00	Rupees Eighteen Thousand Only

I am prepared to execute the above mentioned work written by me in Schedule - B

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Contractor Signature
Reg. No.
Postal Address

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92
12/03

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

12/03